

BaH molecular spectroscopy with relevance to laser cooling

M. G. Tarallo, G. Z. Iwata, and T. Zelevinsky*

Department of Physics, Columbia University, 538 West 120th Street, New York, New York 10027-5255, USA

(Received 17 December 2015; published 17 March 2016)

We describe a simple experimental apparatus for laser ablation of barium monohydride (BaH) molecules and the study of their rovibrational spectra relevant to direct laser cooling. BaH is a promising candidate for laser cooling and ultracold fragmentation, both of which are precursors to novel experiments in many-body physics and precision measurement. We present a detailed analysis of the properties of ablation plumes that can improve the understanding of surface ablation and deposition technologies. A range of absorption spectroscopy and collisional thermalization regimes has been studied. We directly measured the Franck-Condon factor of the $B^2\Sigma^+(v'=0) \leftarrow X^2\Sigma^+(v''=1)$ cycling transition. Prospects for production of a high luminosity cryogenic BaH beam are outlined.

DOI: [10.1103/PhysRevA.93.032509](https://doi.org/10.1103/PhysRevA.93.032509)**I. INTRODUCTION**

The study of diatomic molecule spectra has a long-standing tradition in many research areas from physical chemistry to astrophysics and nuclear physics [1]. Precisely characterizing the molecular level structure is crucial for expanding the scope of applications for these physically rich systems. Many diatomic species of interest, because of their high reactivity, must be produced in the laboratory from gaseous or solid precursors, or probed via astronomical observations. Among these, the light diatomic hydrides, and in particular alkaline-earth-metal hydrides, are of great importance for the understanding of chemical bonding because of their amenability to theoretical treatment. These molecules are also ideal candidates for direct laser cooling [2] and production of a polar molecule gas near absolute zero [3], as well as for ultracold fragmentation for improved precision measurements with hydrogen isotopes [4].

In this work we study the production and spectral properties of barium monohydride (BaH) that are relevant to laser cooling. Figure 1 shows the electronic, rovibrational, and spin structure important for molecular laser cooling. Multiple studies have been performed on the BaH electronic ground state, $X^2\Sigma^+$, and seven excited electronic states [5–10]. The two lowest excited electronic states, $A^2\Pi$ and $B^2\Sigma^+$, lie in the near infrared spectral region, and both can be accessed by commercially available diode lasers. Furthermore, they both exhibit highly diagonal decay to the ground state [2,11], which is crucial for laser cooling. In fact, the $A^2\Pi$ and $B^2\Sigma^+$ states may enjoy complementary laser cooling and trapping advantages: the former is predicted to have more favorable decay branching ratios [4], while the latter has a large magnetic moment that should ensure much stronger magneto-optical trapping forces [12]. Laser cooling has been attempted with $A^2\Pi$ molecular states [13–15], and here we focus on the $B^2\Sigma^+$ state of BaH. While previously BaH was mainly produced in hydrogen furnaces [8], we present a simple approach to precise spectroscopy of BaH molecules, as well as many other diatomic species, that is directly applicable to buffer-gas cooled molecular beams [16,17] that are used for loading molecular magneto-optical traps (MOTs) [14,18]. The BaH gas is obtained from

a solid BaH₂ precursor by pulsed laser ablation in a small vacuum chamber constructed from standard components.

The paper is organized as follows. In Sec. II we describe the experimental setup used to produce and probe BaH dimers. In Sec. III we model the time- and frequency-resolved laser absorption of the ablation plume with and without a buffer gas. Next, the experimental results are shown in Sec. IV, where we also characterize the molecular yield and thermal properties as functions of the ablation laser fluence, along with a Franck-Condon factor measurement via nonlinear absorption. Finally, in Sec. V we discuss the considerations and implications for laser cooling BaH molecules.

II. LASER ABLATION AND SPECTROSCOPY SETUP

The experimental apparatus is sketched in Fig. 2. The ablation chamber consists of a standard four-way cross with three optical windows and a port leading to the vacuum pump. The focused Nd:YAG (yttrium aluminum garnet) ablation laser (BigSky Ultra) light at 1064 nm (50 mJ/pulse) enters through the central window and hits the target glued to the holder at the center of the cross. The resulting ablation plume is probed along the perpendicular axis. The fluence of the ablation light impinging on the target can be varied by adjusting the focusing lens position. The laser repetition rate is typically set to 2 Hz and the measured pulse width is below 10 ns. Probe light is produced by an extended-cavity diode laser (ECDL) in a Littman-Metcalf configuration, and is tunable between 904 and 914 nm. We perform precise laser absorption spectroscopy (LAS) on the ablated plume of molecules by monitoring the probe laser extinction level after ablation. Beam splitters in Fig. 2 allow counterpropagating two-beam LAS for precise measurements of the Doppler shift.

The probe light is detected by a fast photodiode with a narrow-band (10 nm) interference filter which prevents ablation fluorescence from saturating the detector. Absorption signals are then recorded by a digital oscilloscope with a response time of 5 ns, which is triggered by the ablation laser Q -switch clock signal. The recorded time-of-flight (TOF) absorption profile allows us to measure the time evolution of the molecule density along the probe beam in a chosen rotational state. Precise probe wavelength control is achieved with a 0.01 pm resolution wavemeter. The setup allows for a controlled variation of many experimental parameters

*tz@phys.columbia.edu




FIG. 1. (a) Electronic and vibrational level structure for two possible laser cooling transitions in BaH. Straight lines represent laser driven transitions, while wavy lines represent radiative decay. $R_{v''\nu'}$ are the calculated branching ratios [4]. (b) Rotational and spin structure of the $B^2\Sigma^+(\nu' = 0) \leftarrow X^2\Sigma^+(\nu'' = 0)$ transition that is relevant to laser cooling.

including the ablation beam focus, ablation angle, probe beam size, and distance between the probe beam and the target.

The molecular targets are commercially obtained solid pieces of BaH₂ with 99% purity that we glue to the holder such that the side facing the ablation laser is as flat as possible. We have also performed ablation spectroscopy on atomic Yb and Sr for comparison and calibration purposes. Finally, buffer gas can be introduced into the chamber through an inlet just before the vacuum pump valve, and the background and buffer gas pressure are monitored by a vacuum gauge (combination Pirani and cold cathode).

III. MODELING ABSORPTION SPECTROSCOPY WITH ABLATED MOLECULES

Resonant LAS is a straightforward method to characterize laser ablation [19–22]. Starting from a basic model to describe




FIG. 2. Schematic drawing of the ablation test chamber and spectroscopy setup. HWP: half-wave plate; PD, photodetector; SF: spectral filter; TMP: turbomolecular pump; VVG: variable voltage generator; ECDL: extended-cavity diode laser. The inset illustrates the experimental geometry in proximity to the target and the resulting ablation plume with a forward speed u at time t . The probe beam is nearly normal to the plume. x_w : position of the chamber window; L : distance from the target to the probe beam; t/β : typical width of the plume.

the molecular ablation plume, in this section we discuss the time- and frequency-resolved LAS signals to characterize the physical properties of the molecular yield and study its internal energy spectra.

A. Time-resolved resonant absorption by the ablation plume

An example of time-resolved absorption due to the transit of the ablation plume through the probe beam is shown in Fig. 3. We clearly observe a dependence of the absorption peak shape and position on the probe distance L . The peak shift yields the center-of-mass molecular speed with respect to the line of sight. By modeling the observed signal we reconstruct the fundamental kinetic quantities that characterize the molecular ablation process: temperature, forward velocity, and the initial density.

The processes leading to pulsed-laser generated gas clouds have been extensively studied and modeled for thin film deposition [23,24]. We begin with a widely accepted hydrodynamical model [25] which consists of an initial elliptical gas cloud generated by desorption from a surface plasma that rapidly equilibrates to a full Maxwell-Boltzmann distribution. In the coordinate system defined in Fig. 2, this is described by

$$p(\vec{v}, T, u) = \frac{\beta^3}{\sqrt{\pi^3}} \exp[-\beta^2(v_x^2 + v_y^2 + (v_z - u)^2)], \quad (1)$$




FIG. 3. TOF absorption signals (blue and black curves) of the BaH ablation plume recorded at different distances L of the probe laser from the target surface. The red lines represent the best fit to the data according to Eq. (3).

which is moving with a stream velocity \vec{u} normal to the target surface. In Eq. (1), $\beta = \sqrt{M/(2k_B T)} \equiv v_{\text{th}}^{-1}$ is the inverse of the most probable thermal velocity, M is the molecular mass, and T is the temperature after the equilibration time t_{eq} . The effective temperature of an ablated diatomic molecule is $T \sim 0.8T_s$ [26], where T_s is the ablation surface temperature.

The collisionless free expansion of an atomic or molecular gas can be described by solving the Boltzmann equation for the phase-space distribution $f(\vec{x}, \vec{v}, t) = f_0(\vec{x} - \vec{v}t, \vec{v})$, where f_0 is the phase-space density at time $t = 0$. For a rapidly equilibrating ejection process, $f_0(\vec{x} - \vec{v}t, \vec{v}) = p(\vec{v}, T, u)n_0(\vec{x} - \vec{v}t)$, where $n_0(\vec{x})$ is the initial spatial distribution. Because of the Gaussian shape of the pulsed laser beam profile, the initial density distribution is a two-dimensional Gaussian function with radius w_{pl} . We find the density function for a freely expanding gas governed by a shifted Maxwell-Boltzmann distribution (1) via $n(\vec{x}, t) = \int d\vec{v} p(\vec{v}, T, u)n_0(\vec{x} - \vec{v}t)$. The finite ablation area introduces a time scale $t_{\text{eq}} = w_{\text{pl}}\beta \approx 200$ ns for the expanding gas to fully equilibrate (assuming $T = 2000$ K, $w_{\text{pl}} = 100$ μm). For $t \gg t_{\text{eq}}$, the density function $n(\vec{x}, t) \propto t^{-3} \exp\{-\beta^2[x^2 + y^2 + (z - ut)^2]/t^2\}$ exhibits a t^{-3} asymptotic behavior as predicted in Ref. [25].

From the time dependence of the plume density, we can calculate the probe absorption. Since the probe laser with a Gaussian width w and intensity I crosses the ablation plume perpendicularly, the absorption signal is a TOF density measurement integrated over the x transverse direction. The Beer-Lambert law, $-dI/I \approx n(\vec{x}, t)\sigma(\omega)dx$, where $\sigma(\omega)$ is the frequency-dependent light-matter interaction cross section, describes absorption in the unsaturated regime. To calculate the photodetector signal, given by the change in probe laser power P_0 , we integrate over y and z , which results in the time-resolved fractional absorption

$$\begin{aligned} \frac{\Delta P(t)}{P_0} &\equiv \mathcal{A}(t) \\ &= 1 - \frac{\sigma(\omega)}{P_0} \int_{-\infty}^{\infty} \int_{-\infty}^{\infty} \int_{z=0}^{\infty} n(\vec{x}, t) I(y, z) dx dy dz. \end{aligned} \quad (2)$$

Therefore,

$$\mathcal{A}(t) \approx \frac{N_0 \sigma(\omega) \beta^2}{\pi t^2} e^{-[(L-ut)^2 \beta^2 / t^2]}, \quad (3)$$

where we have simplified the full expression for $L > w/\sqrt{2}$, $t > \beta w$. Note that $\mathcal{A}(t \rightarrow \infty) \propto 1/t^2$, implying that TOF absorption signals fall off slower than fluorescence signals ($\propto 1/t^3$) [21]. Equation (3) can be used to fit the TOF profiles as in Fig. 3. The molecular yield can be estimated as

$$N_0 \approx \mathcal{A}(t_p) \frac{e^{(L-t_p/u)^2 \beta^2 / t_p^2} \pi t_p^2}{\sigma(\omega) \beta^2}, \quad (4)$$

where t_p is the time at which the fractional absorption reaches its peak value. Equivalently, the yield can be expressed in terms of the initial density by considering that $N_0 \approx \pi n_0 v_{\text{th}} w_{\text{pl}}^2 \delta t_p / 2$, where the emission time δt_p is assumed to be on the order of the laser pulse width [19].

B. Frequency-dependent absorption and saturation effects

The fractional probe absorption at t_p is proportional to the cross section $\sigma(\omega)$. In addition to the natural linewidth, the frequency dependence of $\sigma(\omega)$ must include the Doppler shift of the probe laser frequency with respect to the moving particles. Integration of Eq. (3) over the velocity distribution (1) yields a fractional absorption spectrum [27]

$$\mathcal{A}(\omega) \propto \sigma(\omega) \equiv \sigma_{lu}^0 \frac{c\beta}{\omega_0 \sqrt{\pi}} e^{-\beta^2 [c(\omega - \omega_0) + u \omega_0 \sin \theta]^2 / \omega_0^2}, \quad (5)$$

which is the Gaussian line shape of the absorption cross section with a full width at half maximum $\Delta\omega = \sqrt{8 \ln(2) k_B T \omega_0^2 / (Mc^2)}$ and a Doppler shifted center due to the misalignment angle θ . Here, $\omega_0 = 2\pi c/\lambda_0$ is the angular frequency of the optical transition resonance, and c is the speed of light. Because of the $\Delta\omega(T)$ dependence, a measurement of the absorption spectrum provides a direct determination of the transverse translational temperature of the ablation plume.

We have introduced the integrated cross section

$$\sigma_{ul}^0 = \frac{g_u \lambda_0^2}{g_l} A_{ul},$$

where A_{ul} is the spontaneous emission rate from the upper to the lower molecular level, and g_u, g_l are the respective degeneracies. Hence a measurement of the absorption cross section at resonance, $\sigma(\omega_0) = \sqrt{8 \ln 2} \sigma_{ul}^0 / \Delta\omega$, provides information on the spontaneous decay process occurring in the electronic transition. This would require an *a priori* knowledge of the ablation molecular yield. However, the strength of the $B-X$ ($v' = 0, v'' = 0$) band can be estimated by measuring the saturation intensity at which nonlinear absorption takes place [28].

The standard saturation intensity is

$$I_s = \frac{g_l}{g_u} \frac{\pi h c}{\lambda_0^3 \tau} \frac{1}{r(J'', N'') R_{00}}, \quad (6)$$

where $\tau = 125(2)$ ns is the lifetime of the $B^2\Sigma(v=0)$ state [29], R_{00} is the vibrational branching ratio which is proportional to the Frank-Condon factor q_{00} , and $r(J'', N'')$ is the rotational branching ratio for the dipole transition moment

of the excited rotational level $|N', J'\rangle$ to a particular rotational level $|N'', J''\rangle$ of the X state. The rotational branching ratio can be expressed in terms of the Hönl-London factor $\mathcal{S}_{J'N', J''N''}$ as [30]

$$r(J'', N'') = \frac{\mathcal{S}_{J'N', J''N''}}{(2J' + 1)}. \quad (7)$$

For transient laser absorption by an ablation plume, the reduction of the cross section due to Doppler broadening and the transit time $\tau_t = 2w/v_p$ taken by the density peak to pass through the probe laser must be included in the calculation. Saturation effects can be modeled by solving the rate equations for the level populations in the time interval $\Delta t \sim 2\tau_t$ centered on the peak of the temporal absorption signal, in which the total number of particles remains constant [31]. The rotational state $|B, J' = 0.5, N' = 0\rangle$ forms a quasiclosed three-level system with the two rotational levels $N'' = 1$ of the first two vibrational bands in the electronic ground state X , since $R_{00} + R_{01} \approx 1$ (Fig. 1). In this case, the effective saturation intensity is

$$I_s^{00} \simeq I_s \frac{1.2 \Gamma_t \Delta \omega}{\Gamma^2} \frac{\Gamma + \Gamma_t}{[1 - r(J'', N'')R_{01}]\Gamma + 3\Gamma_t}, \quad (8)$$

where $\Gamma_t = 1/\tau_t$ is the transit time broadening and $\Gamma = 1/\tau$ is the total radiative relaxation rate.

Another method to measure the excited state branching ratios is to introduce a second laser to probe the $B-X(0,1)$ transition. Its fractional absorption \mathcal{A}_{01} will depend on the presence of the driving laser on the $B-X(0,0)$ transition. For low intensities, we can approximate the fractional absorption from Eq. (3) as $\mathcal{A}_{00} \approx n(t_p)\sigma_{00}(\omega_{00})\Delta x(1 - s_0)$ over an effective thickness Δx of the absorbing gas, where s_0 is the saturation parameter. While stand-alone absorption on the $(0,1)$ band depends on the population of the first excited vibrational state, the differential absorption due to the presence of the $B-X(0,0)$ driving laser can be related to all accessible quantities as

$$\Delta \mathcal{A}_{01} = \mathcal{A}_{00}^0 \chi(\Gamma, \Gamma_t, f_1, R_{01}) s_0 \left(\frac{\lambda_{01}}{\lambda_{00}}\right)^3 \frac{R_{01}}{1 - R_{01}}, \quad (9)$$

where \mathcal{A}_{00}^0 is the absorption of the $(0,0)$ laser without the additional probe beam, and

$$\chi = 1 + \frac{f_1[(1 - r)\Gamma + 5\Gamma_t] - 5\Gamma_t}{(1 - f_1)[(1 - rR_{01})\Gamma + 3\Gamma_t]}$$

is a function of the initial population fraction in the first excited vibrational level, f_1 , which takes on positive values between 0.4 and 1.

Equations (8) and (9) provide two independent experimental methods to estimate the vibrational branching ratio $R_{01} = q_{01}(\omega_{01}/\omega_{00})^3$, and thus the vibronic Franck-Condon factor q_{01} . A small value of q_{01} is a prerequisite for direct laser cooling.

IV. RESULTS

A. Thermal properties and molecular yield of the ablation plume

Measurements of the BaH molecular yield and translational temperature are shown in Fig. 4(a) as a function of the 1064 nm pulsed ablation laser fluence. The probe laser was




FIG. 4. Experimental characterization of the molecular temperature via frequency-resolved LAS. (a) Translational temperature and molecular yield as functions of the ablation laser fluence. (b) Relative absorption amplitudes of the P_2 rotational states. The bar heights represent the measured line absorption normalized according to Eq. (7).

tuned to the $P_2(J'' = 4.5)$ transition (see Sec. IV C). We clearly observe the ablation threshold around 10 J/cm^2 at which the $|N'' = 5, J'' = 4.5\rangle$ state population is $\sim 10^7$. The ablation threshold depends on the physical properties of the target surface such as hardness, roughness, and reflectivity. Both the hardness and the density ($\lesssim 3 \text{ g/cm}^3$) of our BaH₂ chunks are low compared, for instance, to metallic Yb or hot pressed targets. Hence we expect a large potential for improvement by switching to hard targets of BaH₂ (4 g/cm^3 [32]) as done in Ref. [33] for CaH molecules. Currently, shot-to-shot fluctuations of up to 25% are observed in the molecular ablation yield, and therefore in typical absorption measurements we average at least four ablation pulses. We also observed a dependence of the molecular yield both on the pulsed laser repetition rate f_r and on the number of shots on the target. For a laser fluence of 16 J/cm^2 , the initial yield is nearly constant from $f_r = 1$ to 15 Hz , and then diminishes, while the shot-to-shot degradation rate depends linearly on f_r , with a characteristic decay constant $\tau(f_r = 2 \text{ Hz}) \approx 2000$ shots. Surprisingly, at $f_r = 15 \text{ Hz}$, after ~ 100 laser pulses and the associated decay of the yield, the signal increased to roughly twice its starting strength. We interpret this as the

constant heating of the target due to a weak thermal link to its environment. At $f_r = 20$ Hz, we also observed a two-peak absorption profile due to thermal desorption of the hot surface after the first ablation event.

The translational temperatures of the ablated molecules versus fluence were recorded by measuring the Doppler widths of absorption profiles. The minimum temperature of ~ 1800 K was measured at 16 J/cm^2 , corresponding to a molecular yield of 1.4×10^8 and a forward velocity $u \approx 910$ m/s. For higher fluence we observed a linear increase of the translational temperature. The extrapolated temperature at the ablation threshold is ~ 1500 K. This estimate is in fair agreement with previous experiments on BaH gases created in furnaces with hydrogen atmosphere, which indicated that BaH₂ has a decomposition point near 1300 K [34].

The distribution of the total population among the rotational ground states $|N'', J''\rangle$ is determined from the relative strengths of observed absorption lines. These strengths are related to the Maxwell-Boltzmann distribution via the rotational temperature T_r [1]. A measurement of the rotational temperature using the P_2 branch is shown in Fig. 4(b). The best fit yields $T_r \approx 400$ K, one order of magnitude lower than the translational temperature. Discrepancies between translational and rotational temperatures in ablation plumes have been reported [35], and confirm the nonthermal origin of ablation. By using this rotational temperature, we can estimate the total molecular yield as

$$N_{\text{tot}} \approx N_J \frac{(2S+1)k_B T_r}{(2J+1)hcB_X} \exp\left[\frac{hcF(N)}{k_B T_r}\right] \sim 3 \times 10^9,$$

where the effective rotational spacing $F(N) = B_X N^2 + (B_X - \gamma_X/2)N - \gamma_X/2$ takes into account the spin splitting of the transition branch. Here, B_X and γ_X denote the rotational energy and spin-rotation energy equilibrium constants for the X state.

The total molecular yield we obtained is similar to that of other alkaline-earth hydride beam experiments [36,37]. For a single-stage cryogenic buffer gas cell the maximum experimental extraction efficiency in the hydrodynamic regime is $\sim 50\%$ [17], thus $N_{\text{tot}} \sim 1.5 \times 10^9$ molecules/pulse could be expected for a cryogenic beam.

B. Diffusion and cooling with room-temperature buffer gas

We have studied the possibility of reducing the Doppler broadening of the molecular spectra, and at the same time conducted an initial investigation of the BaH collision cross sections with noble gases, by filling the ablation chamber with buffer gas at room temperature ($T_{\text{bg}} = 297$ K). The buffer gas dissipates both the translational and rotational energies. Translational cooling relies on elastic collisions, but inelastic scattering contributes to rotational thermalization. This can explain the small difference between rotational and translational temperatures measured in cryogenic buffer-gas molecular beams [38].

1. Translational cooling

The dynamics of an ablation plume produced inside a background gas has been studied in a variety of systems. It can be divided into two phases: an initial ballistic expansion

of the plume away from the target, followed by diffusion which depends inversely on the buffer gas pressure [39]. During both phases, thermalization of the plume with the buffer gas occurs [36]. The translational thermalization with an inert buffer gas has been modeled by assuming elastic collisions between two hard spheres of mass m (buffer gas) and M (ablated species). In a hard-sphere model, from energy and momentum conservation the average temperature change per collision event is $\Delta T = -\kappa(T - T_{\text{bg}})$, where $\kappa \equiv (M+m)^2/(Mm)$. This implies the ablation plume temperature evolution [40]

$$\frac{dT}{dt} = -R(T - T_{\text{bg}})/\kappa, \quad (10)$$

where $R = n_{\text{bg}}\sigma_{\text{BaH,bg}}\bar{v}$ is the elastic collision rate determined by the buffer-gas density $n_{\text{bg}} = p/(k_B T_{\text{bg}})$ with p being the gas pressure, the thermally averaged collision cross section $\sigma_{\text{BaH,bg}}$, and the average relative speed

$$\bar{v} = \sqrt{\frac{8k_B}{\pi} \left(\frac{T}{M} + \frac{T_{\text{bg}}}{m} \right)} \sim \sqrt{\frac{8k_B T}{\pi \mu}}.$$

The translational temperatures can be determined by recording Doppler-broadened spectra for BaH molecules. Figure 5(a) shows typical Doppler temperatures measured at different time intervals from the ablation pulse in the presence of room-temperature He buffer gas. The inset features two spectra: one without the buffer gas and corresponding to the initial temperature, and another one after a $1.1 \mu\text{s}$ TOF. The temperature follows an exponential decay, as predicted by Eq. (10), for both He and Ar buffer gasses. The fitted thermalization rates are used to estimate the elastic cross sections $\sigma_{\text{BaH,He}} = (0.31 \pm 0.02) \times 10^{-20} \text{ m}^2$ and $\sigma_{\text{BaH,Ar}} = (8 \pm 3) \times 10^{-20} \text{ m}^2$. The result for Ar is similar to the previously measured $\sigma_{\text{YbF,He}}$, which has been found to underestimate the actual cross section by an order of magnitude [39].

Another method to estimate the cross section consists of measuring the diffusion time constants from time-resolved absorption. Figure 5(b) shows the evolution of BaH absorption 3.5 mm from the target with the Ar buffer gas pressure. By fitting the tails of the absorption profiles with an exponential decay we estimate $\sigma_{\text{BaH,Ar}}^{(\text{D})} \approx (19 \pm 9) \times 10^{-20} \text{ m}^2$. It is clear from the profiles that for times longer than the typical ballistic arrival time ($\sim 10 \mu\text{s}$) the data is dominated by technical noise, which suggests that $\sigma_{\text{BaH,Ar}}^{(\text{D})}$ should be considered a lower bound (further suggesting that cross sections were underestimated via the Doppler method). For comparison, we repeated the diffusion measurement with ablated Yb atoms. The resulting cross section is $\sigma_{\text{Yb,Ar}}^{(\text{D})} = (1.9 \pm 0.1) \times 10^{-17} \text{ m}^2$, improving the previously reported upper limit for Yb-Ar elastic collisions [41].

The BaH-He elastic cross section, $\sigma_{\text{BaH,He}}$, is a crucial parameter for determining the brightness of a He buffer-gas cooled beam of BaH. The beam extraction efficiency of a molecule from the buffer-gas cell can be characterized by the dimensionless ratio, γ_{cell} , between the time it takes a diffusing molecule to stick to the cell wall and the He exit time from the cell [17]. The brightest beams (up to 50% extraction efficiency) are achieved with $\gamma_{\text{cell}} > 1$ [42]. This ratio is directly proportional to $\sigma_{\text{BaH,He}}$ and the buffer-gas density, therefore the comparatively low value of $\sigma_{\text{BaH,He}}$ can




FIG. 5. Translational cooling and diffusion of ablated BaH by a buffer gas. (a) Spectral widths of the absorption resonance have been measured at different TOFs in the presence of He, showing good agreement with exponential decay. The inset demonstrates the change of the absorption spectrum without the buffer gas (red squares) and after a 1.1 μs TOF (blue circles). (b) The transition from ballistic to diffusive expansion of BaH molecules in an Ar buffer gas.

be compensated by cell geometry (such as the volume or target positioning) and experimental parameters that optimize the buffer-gas density.

2. Rotational thermalization

In addition to translational cooling, we studied the evolution of an initial nonthermal rotational distribution of BaH, described in Sec. IV A, in the presence of a buffer gas. The rotational temperature T_r is estimated by fitting a Boltzmann distribution to the relative strengths of the P_2 absorption lines originating from the lowest 11 ground-state rotational levels ($J = 1.5$ – 11.5), as shown in Fig. 6(a).

Collisions of BaH with both Ar and He buffer gases at room temperature lead to absorption enhancement at higher J and a better agreement with a thermalized Maxwell-Boltzmann distribution. For Ar buffer gas, $T_r = 860 \pm 140$ K at $p = 0.79$ torr after 5 μs TOF, while for He, $T_r = 480 \pm 40$ K at $p = 40$ torr after 2 μs TOF. This result is in agreement with




FIG. 6. Rotational cooling of ablated BaH by Ar and He buffer gases. (a) P_2 absorption lines for various ground-state rotational levels, for determining the rotational temperatures with and without a room-temperature buffer gas. (b) The measured translational and vibrational thermalization for room-temperature Ar at the density of $2 \times 10^{22} \text{ m}^{-3}$, along with the fitted translational thermalization curve (black solid line) and the rotational thermalization curve with a thermalization rate chosen to best describe the data (blue solid line, with dashed lines showing the range consistent with the data).

a thermalization process modeled by an exponential decay with the equilibrium temperature set by the instantaneous translational temperature. In the case of Ar that is shown in Fig. 6(b), the rotational thermalization time is about $7 \pm 2.5 \mu\text{s}$ —about twice the estimated translational thermalization time—in agreement with previous results that report rotational cross sections smaller than or similar to the corresponding elastic cross-section values [16,39].

C. Precise rovibrational spectroscopy of the $B-X(0,0)$ band

We have performed precise rotational spectroscopy of the $B^2\Sigma^+(v' = 0) \leftarrow X^2\Sigma^+(v'' = 0)$ electronic transition by measuring the absorption lines of the two P branches ($\Delta J = \Delta N = -1$) and the satellite $^PQ_{12}$ branch ($\Delta J = 0, \Delta N = -1$). The identification of the observed resonances was based on the lines reported in Ref. [6] and on the values expected

TABLE I. The measured transition lines and a comparison with previous data for P_1 , P_2 , and ${}^PQ_{12}$ branches. The uncertainties represent a combination of statistical and systematic error. The last column summarizes the differences between our high-resolution measurements and Ref. [8].

	J''	This work (nm)	Prior work [6] (nm)	Theory [8] (nm)	Difference (pm)
P_1	1.5	905.31970(3)	–	905.32024	–0.54(3)
	2.5	906.09010(8)	906.0991	906.09132	–1.22(8)
	3.5	906.88122(4)	906.8896	906.88223	–1.01(4)
	4.5	907.69219(3)	907.6947	907.69279	–0.60(3)
	5.5	908.52230(4)	908.5375	908.52281	–0.51(4)
	6.5	909.37130(3)	909.3769	909.37212	–0.82(3)
	7.5	910.23967(7)	910.2295	910.24055	–0.88(7)
	8.5	911.12713(6)	911.1335	911.12796	–0.83(6)
	9.5	912.03306(3)	912.0310	912.03418	–1.12(3)
	10.5	912.95755(3)	912.9627	912.95912	–1.57(3)
	11.5	913.90056(3)	912.9627	913.90260	–2.04(3)
P_2	1.5	905.46645(3)	–	905.46699	–0.54(3)
	2.5	905.85052(6)	905.8521	905.85112	–0.60(6)
	3.5	906.25389(2)	906.2593	906.25420	–0.31(2)
	4.5	906.67616(4)	906.6816	906.67614	0.02(4)
	5.5	907.11708(4)	907.1307	907.11690	0.18(4)
	6.5	907.57678(3)	907.5851	907.57642	0.36(3)
	7.5	908.05521(3)	908.0656	908.05467	0.54(3)
	8.5	908.55110(2)	908.5590	908.55162	–0.52(2)
	9.5	909.06738(2)	909.0777	909.06724	0.14(2)
	10.5	909.60222(4)	909.6168	909.60153	0.69(4)
	11.5	910.15485(4)	910.1599	910.15449	0.36(4)
${}^PQ_{12}$	0.5	905.29604(2)	–	905.29664	–0.60(2)
	1.5	906.05214(3)	–	906.05193	0.21(3)
	2.5	906.82640(8)	–	906.82702	–0.62(8)
	3.5	907.62107(7)	–	907.62171	–0.64(7)

from the equilibrium constants [8]. The calculated resonance positions assumed that both the X and B states have pure Hund's case (b) couplings. Hence their rotational energies $F_{1,2}(N)$ are split into two submanifolds via the spin-rotation interaction [43],

$$F_{1,2}(N) = BN(N+1) - DN^2(N+1)^2 + HN^3(N+1)^3 \pm \frac{\gamma_N}{2} \left(N + \frac{1}{2} \mp \frac{1}{2} \right), \quad (11)$$

where the subscripts refer to $J = N \pm 1/2$, and the effect of centrifugal distortion is approximated as $\gamma_N = \gamma + \gamma_D N(N+1)$ in terms of the spin-rotation constant γ .

By tuning the mirror angle in our ECDL, we spanned the rotational spectrum of the $B-X(0,0)$ band between 905 and 911 nm. We identified all the P_1 and P_2 branch lines from $J = 1.5$ to 11.5, and ${}^PQ_{12}$ lines from $J = 0.5$ to 3.5. The transition wavelengths are listed in Table I. The measured values deviate from the expected wavelengths by about -180 MHz on average with a standard deviation of 150 MHz, which is consistent with the 200 MHz accuracy of our wavemeter. The sample spectral line shapes in Fig. 7(a) exhibit typical Gaussian widths of ~ 3 pm.

The ground-state spin splitting $\Delta\nu_{ss} = \gamma_X(N+1/2)$ is of particular interest for laser cooling of BaH. It has been




FIG. 7. $B^2\Sigma^+(N'=0) \leftarrow X^2\Sigma^+(N''=1)$ spectroscopy. (a) Determination of the $X^2\Sigma^+(N''=1)$ level spin-rotation splitting. (b) Doppler shift measurement for transverse spectroscopy on the $P_1(1.5)$ cooling transition.

shown that rotational branching is minimized by cooling on the $N' = 0 \leftarrow N'' = 1$ transition [44]. For the excited level $B^2\Sigma^+(N'=0, J'=0.5)$, parity selection rules allow only two possible decay channels (neglecting hyperfine structure): a P_1 transition to $J'' = 1.5$, and a satellite ${}^PQ_{12}$ transition to $J'' = 0.5$ with the same rotational line strength [45]. The measured spectrum of this spin-rotation doublet is shown in Fig. 7(a). The well-resolved line shapes yield the spin-rotation splitting $\Delta\nu_{ss}(N=1) = 8.654(3)$ GHz centered at about 905.3 nm. For the purposes of laser cooling, this splitting can be spanned with existing electro-optical technology.

Particularly precise measurements of both the $P_1(1.5)$ and the ${}^PQ_{12}(0.5)$ transition wavelengths have been performed via Doppler-free interrogation. When present, the Doppler shift is the dominant systematic effect due to the nonzero angle θ between the probe laser propagation and the direction perpendicular to the plume forward velocity, which depends on the positioning of each BaH₂ sample and its surface regularity. We assessed the Doppler shift by aligning a pair of counterpropagating probe beams with mrad precision and probing the ablation plume either simultaneously or consecutively, as shown in Fig. 7(b). The differential absorption signal from the two




FIG. 8. Ground-state (a) spin splitting and (b) P -branch line splitting measurement with low- N levels of the $B-X$ (0,0) band. (c) Combined fit residuals. The gray area represents the 200 MHz wavemeter uncertainty.

photodetectors is centered on the Doppler-free resonant wavelength, while common noise sources such as the ablation yield and laser frequency variations cancel out, increasing the signal-to-noise ratio and leading to an uncertainty of only 3.6 MHz.

It is possible to improve the accuracy of the spin-rotation constant γ_X , which defines the ground state $\Delta v_{ss}(N=1)$, by measuring the frequency difference between each P_1 line and its satellite transition ${}^P Q_{12}$, as well as the line splitting of the two P branches,

$$\Delta v_{12}(P) \equiv P_1(N) - P_2(N) = (\gamma_B - \gamma_X)N - \frac{1}{2}(\gamma_B + \gamma_X) \quad (12)$$

for many values of N . Both the line splitting and the spin splitting data (10 points and 4 points, respectively) were used to determine the spin-rotation constants, as shown in Fig. 8. The resulting values are $\gamma_X = 0.191\,65(88)\text{ cm}^{-1}$, $\gamma_B = -4.7532(12)\text{ cm}^{-1}$, and $\gamma_{BD} = 0.000\,329\,7(55)\text{ cm}^{-1}$ for the centrifugal distortion of B . The ground-state centrifugal distortion constant was neglected because it is expected to be on the order of 10^{-5} cm^{-1} . The agreement with Ref. [8], where the number of recorded transitions is in the hundreds, is at the fourth significant digit for both linear spin-rotation constants.

D. Nonlinear absorption and Franck-Condon factor measurement

We measured the decay branching ratio of the $B(v'=0)$ energy level to the first two ground-state vibrational levels $v''=0,1$ by dual resonant absorption spectroscopy. A laser beam from an additional ECDL tuned to $\lambda_{01} = 1009.43\text{ nm}$ was superimposed onto the 905 nm laser to simultaneously probe the $|B, v'=0, N'=0, J'=0.5\rangle \leftarrow |X, v''=0, N''=0, J''=0.5\rangle$ and $|B, 0, 0, 0.5\rangle \leftarrow |X, 1, 0, 0.5\rangle$ P_1 transitions. A weak resonant absorption signal was observed on the latter transition, both with and without the 905 nm pump laser, as shown in Fig. 9.




FIG. 9. Dual resonant absorption spectroscopy of the $B-X$ (0,0) and $B-X$ (0,1) transitions [$P_1(1.5)$].




FIG. 10. Experimental study of the transient saturation intensity on a BaH molecular plume for different rovibrational transitions. (a) The fractional absorption versus probe laser intensity for the $P_2(J''=4.5)$ and ${}^P Q_{12}(3.5)$ lines. (b) Summary of all the I_s measurements on the P (black squares) and ${}^P Q$ (blue circles) branches of the $B-X$ (0,0) band. Comparison lines with the expected values according to Eq. (8) are drawn.

We used Eq. (9) to estimate the decay branching ratio, assuming that $R_{00} + R_{01} \approx 1$ [4,11]. The saturation parameter s_0 was experimentally determined by varying the pump power and recording \mathcal{A}_{00}^0 , as shown in Fig. 10(a) for two sample transitions. For this particular measurement we used the value $\mathcal{A}_{00}^0 = 0.038(10)$, where the uncertainty represents the large absorption fluctuations. Assuming a thermal vibrational distribution of the molecules ($f_1 = 0.44$ at $T = 7000$ K), the resulting decay branching ratio to the first excited vibrational level is

$$R_{01} = 0.043_{-0.030}^{+0.018} \quad (13)$$

This estimate is in good agreement with *ab initio* calculations [4], and can be also expressed in terms of the Franck-Condon factor $q_{01} = 0.059_{-0.041}^{+0.025}$.

An alternative method of the branching ratio measurement is via the study of saturation intensity $I_s(N'', J'')$, as described in Sec. III B. We performed resonant absorption spectroscopy on several P and PQ lines by varying the probe laser intensity and measured the fractional absorption, as shown in Fig. 10(a). The data is fitted with the function $\mathcal{A} = \mathcal{A}_0/\sqrt{1 + x/I_s(N'', J'')}$ [39].

While the saturation behavior of the absorption signal follows the expected trend, the fitted I_s values show good agreement with Eqs. (8) and (13) for small rotational numbers ($J'' \leq 1.5$), while they disagree at higher J'' values, as shown in Fig. 10(b). For the P branch (PQ branch), the growth with J'' is larger (smaller) than predicted by Eq. (8), which could be explained with a dependence of the total radiative decay rate Γ on the rotational number J'' [29].

V. OUTLOOK

The ablation and spectroscopy described here provide the groundwork needed to create a bright cryogenic molecular beam of BaH, and to laser cool and eventually trap BaH into a molecular MOT. Helium buffer-gas cooling provides a proven starting point for the ultracold molecule production process [36], and our work can be extended to a cryogenic environment where laser-ablated BaH molecules would thermalize with a flowing He buffer gas at 4 K. In particular, Secs. IV A and IV B demonstrate the amenability of BaH to extraction via laser ablation of a solid target and to buffer-gas rotational and translational cooling, both of which are key components of a cryogenic beam. Cryogenic buffer-gas cooling combined with expansion cooling is expected to lead to molecular beam temperatures of 1–4 K, with high ground-state molecule densities of $\sim 10^9/\text{cm}^3$ and low forward velocities of tens of m/s [42].

Figure 1 illustrates two possible laser cooling transitions, $A^2\Pi \leftarrow X^2\Sigma^+$ and $B^2\Sigma^+ \leftarrow X^2\Sigma^+$, focusing on the latter in part (b) since it is expected to be more favorable for creating a MOT. The magnetic g factors of the upper and lower states are comparable in this case, which is the determining factor for the strength of the trapping forces [12]. Each g factor must account for the spin-rotation and hyperfine interactions. The effective molecular g_F with respect to the total angular momentum $\mathbf{F} = \mathbf{J} + \mathbf{I}$ is $g_F \approx g_J[F(F+1) + J(J+1) - I(I+1)]/[2F(F+1)]$, where $g_J = g_s[J(J+1) + S(S+1) - N(N+1)]/[2J(J+1)]$ is the effective spin-rotation g factor for a Hund's case (b) $^2\Sigma$ state, and $g_s = 2$. In the expression for g_F we have neglected the term of order μ_N/μ_B

TABLE II. The g factors relevant to laser cooling BaH on the $B^2\Sigma^+ \leftarrow X^2\Sigma^+$ transition, with and without state mixing between hyperfine states.

State	Ideal case	With state mixing
$X^2\Sigma^+(N=1, J=3/2, F=2)$	0.500	0.500
$X^2\Sigma^+(N=1, J=3/2, F=1)$	0.833	0.836
$X^2\Sigma^+(N=1, J=1/2, F=1)$	-0.333	-0.336
$X^2\Sigma^+(N=1, J=1/2, F=0)$	0.000	0.000
$B^2\Sigma^+(N=0, J=1/2, F=1)$	1.000	0.938
$B^2\Sigma^+(N=0, J=1/2, F=0)$	0.000	0.000

arising from the nuclear magnetic moment, as well as the mixing between different J states which is valid at low external fields. To include the mixing, we solved the Hamiltonian exactly, and the relevant results are listed in Table II. For the $B^2\Sigma^+(N'=0, J'=1/2)$ state, $g_J = 1$, in contrast to the $A^2\Pi_{1/2}$ excited state where $g_J \approx 0$. Therefore, the MOT forces are minimized for any light polarization configuration in the case of $A^2\Pi_{1/2} \leftarrow X^2\Sigma^+$ cooling [12], whereas for $B^2\Sigma \leftarrow X^2\Sigma^+$ cooling we predict a ~ 5 -fold enhancement of the typical molecular optical trapping forces [18,46] without the need for radio-frequency remixing of dark states [14].

BaH has a low-lying $A'^2\Delta_{3/2}$ state (Fig. 1) that can provide a loss channel for molecules cycled through the $A^2\Pi$ or $B^2\Sigma^+$ states [47]. While cooling via $B^2\Sigma^+$ reduces this possibility, it is important to verify that spontaneous decay to the lower-lying electronic states does not significantly limit the number of molecule-photon scattering events. The $B^2\Sigma^+$, $A^2\Pi$, and $A'^2\Delta_{3/2}$ states form a single complex [48], each state possessing Σ , Π , and Δ components in its electronic wave function. Therefore, electronically forbidden $\Sigma \leftarrow \Delta$ transitions may become weakly allowed. Spontaneous decay to $A^2\Pi$ (branching ratio $R_{\Sigma-\Pi}$ in Fig. 1) takes place at the long wavelength of $\sim 6 \mu\text{m}$ and is therefore suppressed by the wavelength factor of $\sim 3 \times 10^{-3}$. In addition, most molecules lost to $A^2\Pi$ are quickly returned to the cooling cycle. The transition moment from $B^2\Sigma^+$ to $A'^2\Delta_{3/2}$ is $\sim 2\%$ of that to the ground state due to a 1% mixing of A and A' [9]. Accounting for the additional wavelength suppression factor, we expect the loss to be sufficiently low. However, the molecules that decay to the A' state are not returned to the cooling cycle, and this loss channel has to be further quantified via quantum chemistry calculations and cryogenic molecular beam experiments.

We experimentally confirmed the small vibrational branching ratio $R_{01} \sim 0.04$, which is favorable for establishing a nearly cycling laser cooling transition. Direct measurements of branching into the higher vibrational levels can be made with the cryogenic molecular beam using laser induced fluorescence [49].

In conclusion, we present precise absorption spectroscopy on an ablation plume of BaH to demonstrate the practicality of laser ablation of these molecules, to investigate their thermalization with buffer gases, and to provide new and improved measurements of the wavelengths and molecular constants needed for operating a BaH cryogenic beam source and for laser cooling. Hyperfine and Zeeman structure will be spectroscopically resolved with a cryogenic molecular beam.

ACKNOWLEDGMENTS

We thank F. Apfelbeck, A. T. Grier, F. Sørensen, and K. Verteletsky for their contributions to this work, and N. R.

Hutzler for helpful discussions. We acknowledge partial support by ONR Grant No. N000-14-1-0802, and G.Z.I. acknowledges support by NSF IGERT Grant No. DGE-1069240.

-
- [1] G. Herzberg, *Spectra of Diatomic Molecules*, Molecular Spectra and Molecular Structure Vol. I (Van Nostrand, New York, 1950).
- [2] M. D. Di Rosa, *Eur. Phys. J. D* **31**, 395 (2004).
- [3] L. D. Carr, D. DeMille, R. V. Krems, and J. Ye, *New J. Phys.* **11**, 055049 (2009).
- [4] I. C. Lane, *Phys. Rev. A* **92**, 022511 (2015).
- [5] W. Fredrickson and W. Watson, *Phys. Rev.* **39**, 753 (1932).
- [6] W. Watson, *Phys. Rev.* **43**, 9 (1933).
- [7] I. Kopp, M. Kronekvist, and A. Guntch, *Ark. Fys.* **32**, 371 (1966).
- [8] O. Appelblad, L. E. Berg, and L. Klynning, *Phys. Scr.* **31**, 69 (1985).
- [9] R. Barrow, B. J. Howard, A. Bernard, and C. Effantin, *Mol. Phys.* **72**, 971 (1991).
- [10] R. Ram and P. Bernath, *J. Mol. Spectrosc.* **283**, 18 (2013).
- [11] M. V. Ramanaiyah and S. V. J. Lakshman, *Physica B+C* **113**, 263 (1982).
- [12] M. R. Tarbutt, *New J. Phys.* **17**, 015007 (2015).
- [13] E. S. Shuman, J. F. Barry, and D. DeMille, *Nature (London)* **467**, 820 (2010).
- [14] M. T. Hummon, M. Yeo, B. K. Stuhl, A. L. Collopy, Y. Xia, and J. Ye, *Phys. Rev. Lett.* **110**, 143001 (2013).
- [15] V. Zhelyazkova, A. Cournol, T. E. Wall, A. Matsushima, J. J. Hudson, E. A. Hinds, M. R. Tarbutt, and B. E. Sauer, *Phys. Rev. A* **89**, 053416 (2014).
- [16] J. F. Barry, E. S. Shuman, and D. DeMille, *Phys. Chem. Chem. Phys.* **13**, 18936 (2011).
- [17] N. R. Hutzler, H.-I. Lu, and J. M. Doyle, *Chem. Rev.* **112**, 4803 (2012).
- [18] J. F. Barry, D. J. McCarron, E. N. Norrgard, M. H. Steinecker, and D. DeMille, *Nature (London)* **512**, 286 (2014).
- [19] M. Harnafi and B. Dubreuil, *J. Appl. Phys.* **69**, 7565 (1991).
- [20] N. Cheung, Q. Ying, J. Zheng, and H. Kwok, *J. Appl. Phys.* **69**, 6349 (1991).
- [21] D. B. Geohegan and D. N. Mashborn, *Appl. Phys. Lett.* **55**, 2345 (1989).
- [22] B. A. Bushaw and M. L. Alexander, *Appl. Surf. Sci.* **127-129**, 935 (1998).
- [23] *Pulsed Laser Deposition of Thin Films*, edited by R. Eason (Wiley, Hoboken, NJ, 2007).
- [24] C. Belouet, *Appl. Surf. Sci.* **96-98**, 630 (1996).
- [25] J. C. S. Kools, T. S. Baller, S. T. De Zwart, and J. Dieleman, *J. Appl. Phys.* **71**, 4547 (1992).
- [26] R. Kelly and R. W. Dreyfus, *Surf. Sci.* **198**, 263 (1988).
- [27] V. Gerginov and C. E. Tanner, *Opt. Commun.* **222**, 17 (2003).
- [28] T. E. Wall, J. F. Kanem, J. J. Hudson, B. E. Sauer, D. Cho, M. G. Boshier, E. A. Hinds, and M. R. Tarbutt, *Phys. Rev. A* **78**, 062509 (2008).
- [29] L. E. Berg, K. Ekvall, A. Hishikawa, and S. Kelly, *Phys. Scr.* **55**, 269 (1997).
- [30] J. K. Watson, *J. Mol. Spectrosc.* **252**, 5 (2008).
- [31] W. Demtröder, *Laser Spectroscopy*, Vol. 2: *Experimental Techniques*, 4th ed. (Springer-Verlag, Berlin, 2008).
- [32] American Elements (private communication).
- [33] H.-I. Lu, J. Rasmussen, M. Wright, D. Patterson, and J. M. Doyle, *Phys. Chem. Chem. Phys.* **13**, 18986 (2011).
- [34] U. Magg, H. Birk, and H. Jones, *Chem. Phys. Lett.* **149**, 321 (1988).
- [35] R. W. Dreyfus, R. Kelly, and R. E. Walkup, *Appl. Phys. Lett.* **49**, 1478 (1986).
- [36] W. C. Campbell and J. M. Doyle, in *Cold Molecules: Theory, Experiment, Applications* (CRC Press, Boca Raton, FL, 2009), pp. 473–508.
- [37] J. D. Weinstein, R. deCarvalho, T. Guillet, B. Friedrich, and J. M. Doyle, *Nature* **395**, 148 (1998).
- [38] N. R. Hutzler, M. F. Parsons, Y. V. Gurevich, P. W. Hess, E. Petrik, B. Spaun, A. C. Vutha, D. DeMille, G. Gabrielse, and J. M. Doyle, *Phys. Chem. Chem. Phys.* **13**, 18976 (2011).
- [39] S. M. Skoff, R. J. Hendricks, C. D. J. Sinclair, J. J. Hudson, D. M. Segal, B. E. Sauer, E. A. Hinds, and M. R. Tarbutt, *Phys. Rev. A* **83**, 023418 (2011).
- [40] R. deCarvalho, J. M. Doyle, B. Friedrich, T. Guillet, J. Kim, D. Patterson, and J. D. Weinstein, *Eur. Phys. J. D* **7**, 289 (1999).
- [41] A. G. Yodh, J. Golub, and T. W. Mossberg, *Phys. Rev. A* **32**, 844 (1985).
- [42] D. Patterson and J. M. Doyle, *J. Chem. Phys.* **126**, 154307 (2007).
- [43] J. M. Brown and A. Carrington, *Rotational Spectroscopy of Diatomic Molecules* (Cambridge University Press, Cambridge, UK, 2003).
- [44] B. K. Stuhl, B. C. Sawyer, D. Wang, and J. Ye, *Phys. Rev. Lett.* **101**, 243002 (2008).
- [45] R. S. Mulliken, *Rev. Mod. Phys.* **3**, 89 (1931).
- [46] D. J. McCarron, E. B. Norrgard, M. H. Steinecker, and D. DeMille, *New J. Phys.* **17**, 035014 (2015).
- [47] M. Yeo, M. T. Hummon, A. L. Collopy, B. Yan, B. Hemmerling, E. Chae, J. M. Doyle, and J. Ye, *Phys. Rev. Lett.* **114**, 223003 (2015).
- [48] A. Bernard, C. Effantin, J. d’Incan, G. Fabre, R. Stringat, and R. Barrow, *Mol. Phys.* **67**, 1 (1989).
- [49] X. Zhuang, A. Le, T. C. Steimle, N. E. Balleid, I. J. Smallman, R. J. Hendricks, S. M. Skoff, J. J. Hudson, B. E. Sauer, E. A. Hinds *et al.*, *Phys. Chem. Chem. Phys.* **13**, 19013 (2011).